



# Southwire™

## RIGID CONCRETE SLAB INSERTS

### 90° - MALLEABLE IRON

#### FEATURES

- Provides flush threaded conduit hub for mounting, pulling and future access to conduit system
- Permits prefabrication of in-slab conduit system

#### APPLICATIONS

- Allows in-slab ceiling drops and floor mounts in poured concrete

#### STANDARD MATERIAL

- Malleable iron

#### CERTIFICATIONS

- cULus Listed (exception ELF125)



EFL50



PART #	SIZE	MASTER QTY.
EFL50	1/2"	10
EFL75	3/4"	20
EFL100	1"	10
EFL125	1-1/4"	10

Rev. 0, 05/23

**BUILT FOR DURABILITY.  
BUILT FOR RELIABILITY.  
BUILT FOR WORK.™**

1-855-798-6657 | SOUTHWIRE.COM

©2023 Southwire Company, LLC. All rights reserved.  
\*Registered Trademark & ™Trademark of Southwire Company, LLC.